BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/RD/WORK_INDENT28240

APPROVED SCHEDULE - B

No. EE/BTP/BBMP/E-PMT/13/2017-18, Date:21.12.2017

Package-7, includes 2 works of Rs.210.00 lakhs

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
1	708.86	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, roads drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up lift 1.5, excavated surface leveled and neatly dressed disposed earth to be leveled after breaking of clods and neatly dressed as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	186.39	Rupees One Hundred Eighty Six and Thirty Nine Paise Only
2	189.17	Removing B.S.slab of Drain and stacking as per the directions of the Engineer-in-charge of the work .	Sqm	73.6	Rupees Seventy Three and Sixty Paise Only
3	229.97	Removing and refixing stone slabs of drains and pointing in CM (1:3) as per the directions of the Engineer-in-charge of the work .	Sqm	90.22	Rupees Ninety and Twenty Two Paise Only
4	38.33	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete as per the directions of the Engineer-in-charge of the work .	Sqm	745.56	Rupees Seven Hundred Forty Five and Fifty Six Paise Only
5	150.84	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete as per the directions of the Engineer-in-charge of the work .	Sqm	924.82	Rupees Nine Hundred Twenty Four and Eighty Two Paise Only
6	45.54	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	97.35	Rupees Ninety Seven and Thirty Five Paise Only
7	811.15	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms as per the directions of the Engineer-in-charge of the work .	Cum	126.31	Rupees One Hundred Twenty Six and Thirty One Paise Only
8	45.54	Providing,laying, spreading and compacting crushed stone aggregates of granite/trap/ basalt to wet mix macadam specification including pre mixing the Material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density. complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	1980.24	Rupees One Thousand Nine Hundred Eighty and Twenty Four Paise Only
9	198	Cleaning the existing WBM Road surface including removing of binding materials and other foreign matter with wire brushes and small picks sweeping with brooms or soft brushes and finally dusting with old gunny bags and bar or compressed air to receive bituminous treatment including cost of all materials, labhour, HOM of machineries complet as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	15.43	Rupees Fifteen and Forty Three Paise Only,
10	198	Providing and applying tack coat using 80/100 grade bitumen (VG 10) on granular base such as WBM surface hot bitumen primed at 4kg per 10 sqm heating bitumen in boiler with spray set (Excluding cleaning of Road surface) inlcuding cost of all materials, labhour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	21.36	Rupees Twenty One and Thirty Six Paise Only

23/06

E.E. (BTP DIV)

23/06

P. Hemanth

Signature of the contractor

Executive Engineer

ved ty.		Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
11	36.38	Providing and laying bituminous macadam on prepared surface with crushed coarse as per design mix formula for base / binding courseincluding loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant,transporting the mixed material in tipper to paver and laying mixed materials, with paver finisher to the required level and grade,rolling by power roller to achieve the desired density,but excluding cost of primer/tack coat including lead,lift and cost of all materials,labour,HOM of machineries complete as per specification and as per the directions of the Engineer-in-charge of the work .	Cum	6421.56	Rupees Six Thousand Four Hundred Twenty One and Fifty Six Paise Only
12	7096.49	Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	3.56	Rupees Three and Fifty Six Paise Only
13	7096.49	Providing and applying tack coat using 80/100 grade bitumen(VG10) in boiler fitted with spray set distributor at the rate of 0.20kg per sqm on the existing prepared bituminous surface cleaned with mechanical broom. complete as per specification and as per the directions of the Engineer-in-charge of the work .	Sqm	10.68	Rupees Ten and Sixty Eight Paise Only
14	311.65	Providing and laying bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site,laying with a paver finisher to the required grade, level and alignment,rolling with smooth wheeled,vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.500.9 complete in all respects complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	10093.57	Rupees Ten Thousand Ninety Three and Fifty Seven Paise Only
15	137.56	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	607.84	Rupees Six Hundred Seven and Eighty Four Paise Only
16	56.75	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specification and as per the directions of the Engineer-in-charge of the work .	Cum	927.2	Rupees Nine Hundred Twenty Seven and Twenty Paise Only
17	56.75	Construction of dry lean cement concrete mix CC1:5:10 with OPC cement @160Kgs, with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum Sub- base over a prepared sub-grade with (coarse and fine aggregate conforming to IS: 383) aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, cement content not to be less than 160 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	4465.05	Rupees Four Thousand Four Hundred Sixty Five and Five Paise Only

23/06

E.E. (BLDG. DIV)

23/06

P. Hemanth

Signature of the contractor

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
18	59.58	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	6964.11	Rupees Six Thousand Nine Hundred Sixty Four and Eleven Paise Only
19	9.7	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Conrete Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms and 2Ltr of Primer per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	768.11	Rupees Seven Hundred Sixty Eight and Eleven Paise Only
20	3	Supplying and fixing fitness related equipments of approved make and international standards including the cost of equipments, transportation, installation at given location etc., complete Spin bike : Providing and fixing of spin bike (GP-333) as per Engineer in Charge of the work. Machine design features proven biomechanics and advanced structural engineering. Quick start key allows commencing exercise with a touch of button. Challenging resistance levels to help you meet your itness goals. Constant heart rate display keeps in the desired training for progressive cardio improving and weight loss. Low maintenance design delivers a fast return of investment. Rotating parts have high quality bearings, are durable in use and there is no noise while using. Heavy gauge welded steel construction. Stayht GP 333 upright bike boasts a beautiful metallic coat inish on a frame of size Dimension 1 5O" (L) X 25"(VV) X 56"(H) Drive System 2 Centre design drive, super silent poly-V belt driven. Pedals 1 Self balanced extra wide pedals with adjustable straps tit to any size user, close spacing , shock Absorbing, air cushion	No	50400.0	Rupees Fifty Thousand Four Hundred Only
21	4	Uprite bike : Providing and fixing of UPRIGHT BIKE (GP-333) as per Engineer in Charge of the work. Machine design features proven biomechanics and advanced structural engineering. Quick start key allows commencing exercise with a touch of button. Challenging resistance levels to help you meet your fitness goals. Constant heart rate display keeps in the desired training for progressive cardio improving and weight loss. Low maintenance design delivers a fast return of investment. Rotating parts have high quality bearings, are durable in use and there is no noise while using. Heavy gauge welded steel construction. Stayit GP 333 upright bike boasts a beautiful metallic coat finish on a frame of size Dimension 2 50" (L) X 25"(VV) X 56"(H) Drive System 1 Centre design drive, super silent poly-V belt driven. Pedals 2 Self balanced extra wide pedals with adjustable straps Ht to any size user, close spacing , shock Absorbing, air cushion and provides gentle movements. Seat 1 Ergonomically designed comfortable seat with flex cushion with 29 levels seat adjustment. Handle Bars 2 U-Bar style with ergonomically elbow support pad and in-built	No	117600.0	Rupees One Hundred Seventeen Thousand Six Hundred Only

P. Hemanth

Signature of the contractor

23/06

E.E. (S&P DIV)

23/06

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
22	4	Cross Trainer : Providing and fixing of Elliptical Cross Trainer (GP-666) - Easier, Il/lore effective Cardio. Stayitl Elliptical Cross Trainer GP- 666 provides a natural, low-impact stride, so users can work out longer and harder. And our design lets them target various muscle groups just by changing the resistance levels. Completely smooth and natural feel Reduces joint stress and minimizes fatigue. Moving handlebars for a total-body workout of Dimension : 8O" (L) X 28"(W) X 7O"(H); Strides 1 20 Inches natural strides. Maximum Watt 1 250 Watts; Resistance Level i 161 Levels. Resistance System 3 Electro-Magnetic resistance; Power I Self generated power system; Programs ; O6 Programs - manual, HRC, random, weight loss, CV and hill interval	No	140000.0	Rupees One Hundred Forty Thousand Only
23	4	Tread Mill : Providing and fixing of Motorised Tread Mill (GP-999) is built for the long run. Our gola was to build treadmill that people would want to use instead of running outside, even if weather conditions were perfect. Ouri engineers have built a revolutionary treadmill that's fully-loaded with patented technology and exclusive performance; features. Our treadmills are powerful running, walking, and jogging machines that are the top choice among exercise enthusiasts around the world. From the basic to the ultimate corporate/club use model, there's nothing like training on a STAYFIT Commercial Series. Stayit treadmills are built to perform to the scrutinizing standards of commercial health club equipment. Compare the features of these extraordinary machines, and you'll discover the qualities that make Stayht the premier name in cardio Htness. Flex Deck Cushioning System - The durable flex deck cushioning system delivers proportional cushioning effects regardless of while using Treadmill. Large Running Surface - The W22" xL 62" running surface provides ample space and is constructed from carbon weave, low friction material that is resistant to static build-up. Powerful Motor - The powerful AC 3.0 HP continuous / 6	No	162400.0	Rupees One Hundred Sixty Two Thousand Four Hundred Only
24	2	Recumbent : Providing and fixing of recumbent bike(GP-333) as per Engineer in Charge of the work. Machinel design features proven biomechanics and advanced structural engineering. Quick start key allows commencingj exercise with a touch of button. Challenging resistance levels to help you meet your fitness goals. Constant heart rate-I display keeps in the desired training for progressive cardio improving and weight loss. Low maintenance design delivers a fast return of investment. Rotating parts have high quality bearings, are durable in use and there is no noise while using. Heavy gauge welded steel construction. Staytit GP 333 upright bike boasts a beautiful metallic coat finish on a frame of size Dimension I 5O" (L) X 25"(W) X 56"(H) Drive System 1 Centre desigm drive, super silent poly~V belt driven. Pedals ; Self balanced extra wide pedals with adjustable straps it to any size user, close spacing , shock Absorbing, air cushion and provides gentle movements. Seat 3 Ergonomically designed. comfortable seat with flex cushion with 29 levels seat adjustment. Handle Bars 1 U-Bar style with ergonomically elbow	No	50400.0	Rupees Fifty Thousand Four Hundred Only
25	80	Dumbbells 20.00/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only
26	70	17.50/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only
27	60	15.00/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only
28	50	12.50/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only
29	40	10.00/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only
30	30	7.50/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only

P. Hemanth

Signature of the contractor

23/06

E.E. (STR DIV)

Executive Engineer

23/06

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
31	20	5.00/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only
32	10	2.50/kgs	kgs	168.0	Rupees One Hundred Sixty Eight Only
33	2	Dumbbell stand : Providing and fixing Dumbbells rack for easy racking and unrocking ., ideal for larger dumbbelh sets easy for pic and place it back hardchorme dumbbells coated with rubber coating for better life and safety with 137cm x47cmx87cm As per engineer incharge of work.	No	28000.0	Rupees Twenty Eight Thousand Only
34	2	Weights stand :Providing and fixing Plate Rack stand of approved make for easy racking and unracking, with rubber coating for better life and safety as per engineer incharge of work	No	28000.0	Rupees Twenty Eight Thousand Only
35	1	Multi Press ; Providing and fixing the equipments rigid body structure plays a critical role in the machine superbl handling Dimensions 3 93"(L) x 44" (W) x 42" (H). Frame 3 High tensile strength steel, continuous welded, factory; assembled weight frame. Tube 1 capsule Tube Size 1 80mm x 50mm main frame. Tube Gauge 1 3.0 mm. Weight Stack 1 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings forl super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods 1 22 mm, chromei 2 plated solid steel, highly policed for smooth movements. Weight Selector Rod 1 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 1 Steel Cablef 3.5mm Jacked with PVC 5.5mm outside diameter Pulley S Nylon, 106 mm x 20 mm diameter with Sealed bearing.&#65533; Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process!Rust Proof: Electro statically applied powder coated. Frame Color: Grey.	No	106400.0	Rupees One Hundred Six Thousand Four Hundred Only
36	1	Lat Pull down : Providing and fixing the equipments rigid body structureplays a critical role in the machine superb, handling Dimensions 1 93"(L) x 44" (W) x 42" (H). Frame 1 I-ligh tensile strength steel, continuous welded, factorw assembled weight frame. Tube 3 capsule Tube Size 2 80mm x 50mm main frame Tube Gauge 3 3.0 mm. Weight! Stack : 80 Kgs Weight Plate ; Cast iron, machine drilled to exact spec and employ oversized nylon bushings forf super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods I 22 mm, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod I 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 3 10 mm gauge steel pin with magnetic knob. Cable 3 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter. Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing Grips 3 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process Rust Proof: Electro statically applied powder coated.	No	112000.0	Rupees One Hundred Twelve Thousand Only

E.E. (STP. DIV) 23/06

P. Hemanth

Signature of the contractor

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
37	1	Mid row : Providing and fixing an equipment of dimensions 93" X 44" X 42" _ Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame. Tube 1 Capsule of size 80mm x 50mm main frame with 3mm gauge. Weight stack 1 80 Kgs , Weight plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushing for super smooth operations. Weight stack guard 1 full front and rear shields. Weight guide rods 1 22 mm, chrome plated solid steel, highly polished for smooth movements, Weight selector rod ; 25mm, chrome plated highly polished for smooth movements, weight selector pin 10mm gauge steel pin magnetic knob, Cable 3 steel cable of 3.5mm jacked with PVC 5.5 mm outside diameter, Pulley 1 Nylon 106mm x 20mm diameter with sealed bearing, Grips 1 Multiple gripping positions, high density rubber hand grips, finishing 3 Proprietary two coat powder process, Rust proof 1 Electro statically applied powder coated. Frame color 1 Grey. Workouts 3 Peres major latissimus dorsi, ramboid major as per Engineer in Charge of the work.	No	112000.0	Rupees One Hundred Twelve Thousand Only
38	1	Shoulder Press: Providing and fixing the equipments rigid body structure plays a critical role in the machine superb handling Dimensions : 93"(L) x 44" (W) x 42" (H). Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame. Tube 1 capsule Tube Size 1 80mm x 50mm main frame. Tube Gauge 5 3.0 mm. Weight Stack 1 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings for super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods 1 22 mrn, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod 1 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 1 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter. Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing. Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process. Rust Proof: Electro statically applied powder coated. Frame Color 1 Grey.	No	106400.0	Rupees One Hundred Six Thousand Four Hundred Only
39	1	Leg Press : Providing and fixing the equipments rigid body structure plays a critical role in the machine superb handling Dimensions 1 93"(L) x 44" (W) x 42" (H). Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame. Tube 1 capsule Tube Size 1 80mm x 50mm main frame. Tube Gauge 1 3.0 mm. Weight Stack 1 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings for super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods 1 22 mm, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod i 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 1 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter. Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing. Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process. Rust Proof: Electro statically applied powder coated. Frame Color: Grey.	No	134400.0	Rupees One Hundred Thirty Four Thousand Four Hundred Only

23/06
E.E. (BTP. DIV)
23/06

P. Hemanth

Signature of the contractor

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
40	1	Leg Extension: Providing and fixing the equipments rigid body structure plays a critical role in the machine superb handling Dimensions 1 93"(L) x 44" (W) x 42" (H). Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame. Tube 1 capsule Tube Size 1 80mm x 50mm main frame. Tube Gauge 1 3.0 mm, Weight Stack 1 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings for super-smooth operations. Weight Stack Guard 1 Full front and rear shields, Weight Guide Rods 1 22 mm, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod 1 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 1 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing. Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing L Proprietary two coat powder process. Rust Proof 1 Electro statically applied powder coated. Frame Color 1 Grey.	No	100800.0	Rupees One Hundred Thousand Eight Hundred Only
41	1	Leg Curl : Providing and fixing the equipments rigid body structure plays a critical role in the machine superb handling Dimensions 1 93"(l_) x 44" (W) x 42" (H). Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame. Tube 1 capsule Tube Size 1 80mm x 50mm main frame. Tube Gauge 1 3.0 mm. Weight Stack 1 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings for super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods 1 22 mm, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod 1 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 1 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter. Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing. Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process. Rust Proof 3 Electro statically applied powder coated. Frame Color 1 Grey.	No	100800.0	Rupees One Hundred Thousand Eight Hundred Only
42	1	Smith Machine : Providing and fixing the equipments rigid body structure plays a critical role in the machine superb handling Dimensions 1 93"(t.) x 44" (W) x 42" (H). Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame Tube 1 capsule Tube Size 1 80mm x 50mm main frame. Tube Gauge 1 3.0 mm. Weight Stack 1 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings for super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods 1 22 mm, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod 1 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 1 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter, Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing. Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process. Rust Proof; Electro statically applied powder coated. Frame Color 1 Grey.	No	168000.0	Rupees One Hundred Sixty Eight Thousand Only
43	1	Pectorial fly machine : Providing and fixing fly machine with overall dimension 46" x 65" x 55" proprietary two coat powder process, internally lubricated cables, full front and rear weight stack guarding sheets, total stack weight of 110 kg, as per standard specification and direction from the Engineer in charge.	No	100800.0	Rupees One Hundred Thousand Eight Hundred Only

P. Hemanth

Signature of the contractor

23/06

Executive Engineer

E.E.

23/06

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
44	1	Oblique rear fly machine : Providing and fixing oblique rear fly machine of size 56" x 54" x 76", frame 1 using high quality steel tube with 125/50 flat elliptical tube or equivalent of guage 3_0 mm, Cable 1 Solid steel wire capable of bearing 1500 Kg, Guide Rod 1 No 45 steel handled by high frequency, hardness, precision to ensure user's safety. Weight Stack 3 92 Kgs, painting 1 powder coating double layer of high quality colour powder.	No	100800.0	Rupees One Hundred Thousand Eight Hundred Only
45	1	Assisted Chinup : Providing and fixing excellent range of 75 kgs weight assisted chinup of 72" x 42" x 88", Frame 1 using high quality steel tube of 120/50 flat elliptical tube or equivalent of guage 3.0 mm, Cable 2 Solid steel wire capable of bearing 1500 Kg, Guide Rod 1 No 45 steel handled by high frequency, hardness, precision to ensure user's safety. Weight Stack 1 92 Kgs, painting 1 powder coating double layer of high quality colour powder.	No	128800.0	Rupees One Hundred Twenty Eight Thousand Eight Hundred Only
46	2	Bench press - declined The equipments rigid body structure plays a critical role in the machine superb handling Dimensions 1 93"(t_) x 44" (W) x 42" (H). Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame. Tube 1 capsule Tube Size 1 80mm x 50mm main frame. Tube Gauge 1 3.0 mm. Weight Stack 1 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings for super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods 1 22 mm, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod 1 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 3 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter. Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing. Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process. Rust Proof 2 Electro statically applied powder coated. Frame Color 1 Grey.	No	44800.0	Rupees Forty Four Thousand Eight Hundred Only
47	2	Bench press - inclined The equipments rigid body structure plays a critical role in the machine superb handling Dimensions 3 93"(l_) x 44" (W) x 42" (H). Frame 1 High tensile strength steel, continuous welded, factory assembled weight frame. Tube ; capsule Tube Size 3 80mm x 50mm main frame. Tube Gauge 1 3.0 mm. Weight Stack ; 80 Kgs Weight Plate 1 Cast iron, machine drilled to exact spec and employ oversized nylon bushings for super-smooth operations. Weight Stack Guard 1 Full front and rear shields. Weight Guide Rods 1 22 mm, chrome plated solid steel, highly policed for smooth movements. Weight Selector Rod 1 25 mm, chrome plated highly policed for smooth movements. Weight Selector Pin 1 10 mm gauge steel pin with magnetic knob. Cable 1 Steel Cable 3.5mm Jacked with PVC 5.5mm outside diameter. Pulley 1 Nylon, 106 mm x 20 mm diameter with Sealed bearing. Grips 1 Multiple gripping positions, high density rubber hand grips. Finishing 1 Proprietary two coat powder process. Rust Proof 1 Electro statically applied powder coated. Frame Color 1 Grey. Workouts 2 Teres major latissimus dorsi, Ramboid Major as per Engineer in Charge of the work.	No	44800.0	Rupees Forty Four Thousand Eight Hundred Only
48	2	Bench press - tlat, with the above same specihcation	No	28000.0	Rupees Twenty Eight Thousand Only
49	4	Bar bell : Providing and supplying barbell of approved make as per the instruction of the Engineer in Charge.(i) 7 feet barbell	No	11200.0	Rupees Eleven Thousand Two Hundred Only
50	4	(ii) 5 feet barbell	No	8400.0	Rupees Eight Thousand Four Hundred Only
51	4	(iii) 3 feet barbell	No	5600.0	Rupees Five Thousand Six Hundred Only

P. Hemanth

Signature of the contractor

23/06

Executive Engineer

E.E. (B.P. DIV)

23/06

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
52	4	(iv) kettler barbell	No	8400.0	Rupees Eight Thousand Four Hundred Only
53	2	Barbel stand : Providing and supplying barbel stand of approved make as per specification.	No	44800.0	Rupees Forty Four Thousand Eight Hundred Only
54	60	Weights : Providing and supplying weights of approved make as per the instruction ofthe Engineer in Charge.20.00/kgs	kgs	195.0	Rupees One Hundred Ninety Five Only
55	45	15.00/kgs	kgs	196.0	Rupees One Hundred Ninety Six Only
56	30	10.00/kgs	kgs	196.0	Rupees One Hundred Ninety Six Only
57	45	7.50/kgs	kgs	196.0	Rupees One Hundred Ninety Six Only
58	50	5.00/kgs	kgs	196.0	Rupees One Hundred Ninety Six Only
59	25	2.50/kgs	kgs	196.0	Rupees One Hundred Ninety Six Only
60	7.5	1.25/kgs	kgs	196.0	Rupees One Hundred Ninety Six Only
61	15	Abodomen mats : Providing mats for abdomen workouts made from premium quality PVC fabrics that ensures its longivity and durability, the mat should be smooth and even finished.i)Long mats - 68" x 24"	No	1680.0	Rupees One Thousand Six Hundred Eighty Only
62	5	ii)Short mats - 48" x 24"	No	1120.0	Rupees One Thousand One Hundred Twenty Only
63	2900	Providing and laying of modular wooden polished flooring of 12 mm thick, high density timber of approved colour and design with end trims, transition, profiles, beading, 15 mm thick felt, and 20 micron polyster Elm with 4mm thick foam underlay etc.,	Sqm	3442.88	Rupees Three Thousand Four Hundred Forty Two and Eighty Eight Paise Only
64	100	Providing and constructing standard rubber flooring for indoor area uising rubber membren of 12mm to 16mm thick,to be layed over prepared cement mortor /concrte surface using cm 1:6 beneath rubber membrane including cost of all materials ,labour ,packing joints and mortor Hnishing curing ,all lead and lift ,transportion and also including all applicable taxes complete as per direction incharge of work.	Sqm	5423.04	Rupees Five Thousand Four Hundred Twenty Three and Four Paise Only
65	500	Providing venyl flooring of approved quality and make, tixed on the top of existing flooring tixed with suitable adeshive, including cutting to the required size and fixing etc, complete	Sqm	618.8	Rupees Six Hundred Eighteen and Eighty Paise Only
66	3	Table Tennis : Supplying and installing Table tennis board approved make,standard size including all the cost transportation, installation etc., completeTables - (3O`-0" X 16'-6")	No	28000.0	Rupees Twenty Eight Thousand Only
67	12	Bats - standard size	No	1008.0	Rupees One Thousand Eight Only
68	36	Balls	No	28.0	Rupees Twenty Eight Only
69	2	Badminton : Supplying and installing Shuttle court related equipments including Fixing of poles, nets etc., complete as per specification Net- 2'-0" high	No	28000.0	Rupees Twenty Eight Thousand Only
70	4	Poles - 5'-1" high	No	2800.0	Rupees Two Thousand Eight Hundred Only
71	8	Shuttle racket- Standard size	No	1680.0	Rupees One Thousand Six Hundred Eighty Only

P. Hemanth

Signature of the contractor

23/06

Executive Engineer

23/06

	Approved Qty.	Description	Unit	Approved Tender Rates of P. Hemanth (M/s. Soorya Creaters)	
				In Figures	In Words
72	15	shuttle cock	No	168.0	Rupees One Hundred Sixty Eight Only
73	25	Yoga Mats :Providing mats for yoga made from premium quality PVC fabrics that ensures its longivity and durability the mat should be smooth and even finished. Mats - 68" long x 24" wide	No	448.0	Rupees Four Hundred Forty Eight Only
74	1	Providing and setting up of a children play yard including all the equipments, sand etc., complete(Lumpsum)	No	184800.0	Rupees One Hundred Eighty Four Thousand Eight Hundred Only
75	2	Providing and supplying commercial RO plant of 100 LPH capacity water purifier system suitable for TDS upto 1500 PPM, multiple purification process, suitable to attend with water cooler, finally automatic optional storage tank box pack of approved make and standards.	No	28000.0	Rupees Twenty Eight Thousand Only
76	1	Providing supplying and fixing to walls 6mm thick mirror and wall papers of best quality including material ,drilling of holes ,bolt and nuts arrengements ,grinding polishing all lift and lead ,labour transportion etc complet as per direction engineer incharge of work	No	56000.0	Rupees Fifty Six Thousand Only
77	1	Providing, supplying and fixing of lockers for changing rooms, special lighting systems for gym 81 other areas and music system with speakers for gym area.	LS	526400.0	Rupees Five Hundred Twenty Six Thousand Four Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

23/06